



# Restoration in Tepee Creek: Lessons Learned and Looking Forward

Will Conley, Hydrologist  
Yakama Nation Fisheries Program

Klickitat / White Salmon Fisheries and  
Watershed Science Science Conference


March 16, 2010

# Outline

- Background
- Tepee IXL Project (phase 1)
  - Results
  - Insights / lessons Learned
    - Bed Material
    - Average Gradient
    - Materials Salvage
- Tepee Creek Meadows (Phase 2)
  - Sequencing
  - Baseline monitoring results

# Location

- Klickitat River tributary
- Columbia R. basin
- south-central Washington State
- east-slope of Cascade Mountains
- 22 miles due east of Mt. Adams
- within Yakama Nation Reservation



# Setting

- Forested watershed (3000-4000')
- Basal geology is Grande Ronde basalt (CRB group)
- Hard parent materials and low to moderate relief = very limited bedload supply
- Contributing drainage area of 8.4 square-miles
- Project reach is at 2965' elevation
- Cohesive soils / banks (Aquandic Haploxeralfs)
- Prevailing soil texture is clay loam

# Problem

- Project reach dried-up in 4 out of 5 years preceding project implementation
- Limited steelhead (ESA- “threatened”) **rearing (limiting)** and spawning habitat
- Fish stranding in ephemeral pools
- Field indicators and hydraulic modeling indicated that project reach was incised 3 to 4 feet, mostly within historic planform

# Goals

- Raise water table / floodplain storage
- Enhance in-channel habitat conditions for rearing steelhead
- Restore suitability of valley bottom for medicinal and traditional food plants

# Project Team

- Will Conley – YN Fisheries Program
  - Project Management
  - Design
  - Construction Oversight
- Mike McAlister, PE - Interfluve, Inc
  - Design
  - Construction Oversight
- Mike Brunfelt - Interfluve, Inc
  - Design
  - Construction Oversight



# Sequencing

Implemented over two field seasons:

## ■ Fall 2006

- All riffles roughed-in
- Downstream grade control completed
- All LWD and rock material delivered to site
- Roughly half of the LWD jams completed
- Temporary erosion control measures implemented

■ Maximum discharge over winter 2006/2007 = 143 cfs

## ■ July 2007

- Final grading on pools and riffles
- LWD jams and floodplain LWD completed
- Revegetation and weed control completed
- Fence construction completed
- Access routes rehabilitated



# Implementation

- A 140' coarsened riffle (0.03 ft/ft) was constructed at the downstream end of the reach for grade-control
- Ninety-five feet of new channel constructed
- Reconnected 135' of historic channel
- Imported gravel to raise bed elevation (~3') and reconstruct pool/riffle sequences along 1850'
- Overall reach lengthened to 1990'
- 28 LWD jams constructed along channel margins
- Numerous floodplain LWD placements constructed
- Removed 2 culverts and related fill from an abandoned cross-valley road alignment

# Typical Riffle Fill and LWD: Under Construction



STA 13+40  
Under construction  
10/20/06

# Typical Riffle Fill: Before & After

8/25/04



STA 6+35

Elevation of constructed  
bank toe / channel invert

5/19/08



5/19/08



## STA 10+60

“Immature” cross-section constructed (2007) to minimize bed shear and allow development of inset channel

Vegetation encroachment after one growing season



11/4/08

8/25/04



STA 12+25

5/4/09



# Ineffective areas intentionally left unfilled

- encourages recruitment of fines
- minimizes suitability for weeds
- hastens colonization by desired hydrophytes



**STA 6+70**

8/7/07

8/25/04



## STA 20+90

(IXL Road Crossing – upstream end of project reach)

Culvert outlets backwatered to improve fish passage




4/5/07

# Groundwater


## Post-project:

- 2' – 4' increase in summer/fall water table
- Less variability between and amongst wells





# Residual Pool Depths



Note: because some pools were under-filled during construction, the median value for residual depths under equilibrium conditions is anticipated to be 2.0' - 2.49'

# Steelhead Spawning



Year	Total Redds in Tepee Creek (redds/mi)	Redds in Tepee IXL Reach (redds/mi)	Redds in Tepee Cr outside of IXL reach (redds/mi)
2004	12 (1.5)	n/a	n/a
2005	0	n/a	n/a
2006	0	n/a	n/a
Project Initiation			
2007	3 (0.4)	2 (5)	1 (0.1)
2008	2 (0.2)	0 (0)	2 (0.3)
2009	12 (1.5)	4 (10)	8 (1.0)

# Results Summary

- Flow Duration: 23 perennial pools maintained all 3 years since construction
- Groundwater: 2 - 4' increase in summer water table
- High Flow Access: at bankfull or lower flows to four side channels totaling 835 lineal feet
- Pools: increased from 15 to 23 (65%); greater depths & cover
- Wetlands: ~3100 ft<sup>2</sup> of emergent wetland created
- Riparian Vegetation: Rapid recovery, particularly of salvaged plant materials
- Spawning: five steelhead redds observed
- Rearing: 2x – 3x increase in juvenile *O. mykiss* abundance
- Macroinvertebrates: Rapid colonization by multiple taxa of caddisflies and mayflies

# Bed Material: Pre-Project



colluvial armor; clasts  $>40\text{mm}$   
mostly sub-angular

bi-modal distribution;  
very high fines content

# Bed Material: Design

## ■ Size distribution should balance:

- stability ( $Q_2 = \sim 150$  cfs)
- porosity ( $Q_{\text{base}} = \sim 10$  gpm)

Percent Smaller Than	Diameter (in)
100	4.0
84	1.8
50	0.7
16	0.2

$$D_{84} / D_{100} = 0.4$$

$$D_{84} / D_{16} = 8.0$$

$$D_{84} / D_{50} = 2.3$$

## ■ Consider:

- Ambient passage conditions
- Temperature vs dissolved oxygen trade-offs
  - D.O. recovers faster than temperature
  - Erred on side of too porous, hence lower potential for adverse temperature and stability effects

# Bed Material: Sourcing

Crushed vs. Alluvium:

- Watershed setting
  - Headwater stream (~8 mi<sup>2</sup> drainage area)
  - Very limited bedload supply is a function of hard basal geology (Grand Ronde basalt) and low relief
  - Bed particles >40 mm are mostly sub-angular
  - Bed particles <40 mm are sub-rounded to rounded and move at flows <  $Q_{AA}$
- What are the project goals?
  - Maintaining vertical elevation of controls (riffle crests) is paramount to success
  - improving spawning habitat NOT a primary goal
- Also consider:
  - Ethics of becoming party to floodplain gravel mining
  - Burning fossil fuels to haul longer distance

# Bed Material: Q Through Riffles

Threshold for wetting



STA 13+20\*

10/30/08

Surface flow at control

~ 0.56 cfs\*\*

11/4/08

Top-to-bottom surface flow

~ 1.90 cfs\*\*

\* STA 13+20 is one of four controls that has a “plug” of native soil in the subgrade

\*\* adult passage and spawning throughout project is comparable to untreated reaches  
(median spawning flow = 12.6 cfs)

# Bed Material: Q Through Riffles

(cont'd)

$Q < 0.5$  cfs




- No subgrade “plug” in either control
- Both stations have comparable cross-sectional fill areas
- STA 2+70 constructed under wetter ambient conditions than 15+80 (i.e. more intrusion of native fines into fill during construction)



# Bed Material: Observations

- Soil plugs in subgrade of riffle crests:
  - Do increase residual pool depths
  - Are as-yet untested in live-bed conditions
- Riffle porosity inversely correlated with:
  - Amount of tracking by equipment
  - Ambient moisture conditions at time of construction
- Fish passage through constructed riffles
  - Is comparable to ambient conditions
- Macroinvertebrate response very positive and rapid
- Steelhead and resident trout spawning observed
- Dissolved Oxygen
  - Appears to be an issue where known groundwater inputs occur and subsurface flow through riffles

# The Thing About Average Gradient...



- Medium to high flows: OK because energy line and bed slope are more or less parallel
- Low flows: energy line is stepped which (in the absence of further treatment) causes headcutting of riffle toes

# Implementing Average Gradient

Mitigate by one or a combination of:

- Skew thalweg to centerline
- Harden / coarsen riffle toe
- Transition slope into head of pool
- Extend riffle downstream into pool
- Add a log drop (only done in one place)



# Native Material Salvage



Vegetation - VERY effective

Gravels - mostly window-dressing (in Tepee Creek)

# Native Material Salvage (cont'd)



STA 14+80



Salvaged sod and shrubs used along bank

# Aspen Regeneration



# Cattle Exclusion



# Microbiotic Recovery



# Tepee – Phase 2

- 7850' reach immediately downstream of IXL reach
- Monitoring (2003-2009) indicates importance to steelhead (ESA “Threatened”)
- Approximately 2/3 of reach dries-up every year
- Design 2009-2010
- Baseline monitoring 2009-2010
- Construction 2010-2011

# Existing Conditions





# Existing Conditions (cont'd)




# Tepee 2 – Monitoring\*


- **Secondary Production**
  - Benthic – Spring, Summer, and Fall
  - Utilization (gastric lavage) - Summer and Fall
  - Drift - Summer and Fall
  - Aerial/Terrestrial - Summer and Fall
- **Salmonids**
  - Adults (spawner and redd counts) - Spring
  - Juveniles/Residents – Summer and Fall
    - Mark-recapture for condition (length & weight)
    - Abundance
    - Migration and survival
- **Physical habitat**
  - Pools, riffles, glides
  - LWD
- **Shallow groundwater – year-round**
- **Surface water**
  - upstream and downstream gages - year-round
  - wetted channel continuity – early fall
- **Vegetation/Ground Cover**
  - Canopy and ground cover
  - Species composition (point-based)

\*conducted cooperatively with YN's Klickitat Monitoring & Evaluation Project


# Fall 2009 Mean Benthic Invertebrate Abundance and Biomass Density in Tepee Creek (Phase 2) Treatment and White Creek Control Sections




# Fall 2009 Benthic Invertebrate Relative Abundance Composition by Order in Tepee Creek (Phase 2) Treatment and White Creek Control Sections



# Fall 2009 Benthic Invertebrate Biomass Composition by Order in Tepee Creek Treatment and White Creek Control Sections



# Summer 2009 Single-Pass Electroshocking Relative Fish Abundance in IXL Tepee (n=1), Phase II Tepee Treatment Sections(n=4), and White Creek Control Sections (n=4)



# Acknowledgements

## IXL Project:

- WA State Salmon Recovery Funding Board  
- materials and construction \$188,192
- Bonneville Power Administration (BPA)  
Klickitat Watershed Enhancement Project  
- materials, planning, design, & oversight \$139,092
- The Yakama Nation (in-kind)  
- LWD \$ 40,650
- Ralph Kiona, Watershed Technician

## Phase 2 Baseline Monitoring

- Nicolas Romero, Fisheries Biologist
- David Lindley, Habitat Biologist

# For More Information

[http://www.ykfp.org/klickitat/KWEP\\_TepeeIXL.htm](http://www.ykfp.org/klickitat/KWEP_TepeeIXL.htm)

